

QPRC



**QUEANBEYAN PALERANG
REGIONAL COUNCIL**

**DEVELOPMENT CONSTRUCTION
SPECIFICATION**

C264

**NON-RIGID ROAD
SAFETY BARRIER SYSTEMS**
(Public Domain)

VERSION 2 – APRIL 2018

TRIM REF: SF140543
C1850654

Amendment Record for this Specification Part

This Specification is Council's edition of the AUS-SPEC generic specification part and includes Council's primary amendments.

Details are provided below outlining the clauses amended from the Council edition of this AUS-SPEC Specification Part. The clause numbering and context of each clause are preserved. New clauses are added towards the rear of the specification part as special requirements clauses. Project specific additional script is shown in the specification as italic font.

The amendment code indicated below is 'A' for additional script 'M' for modification to script and 'O' for omission of script. An additional code 'P' is included when the amendment is project specific.

Amendment Sequence No.	Key Topic addressed in amendment	Clause No.	Amendment Code	Author Initials	Amendment Date
VERSION 1	Inspections requirements added	C264.01.3	A	KD	1/04/10
	Specification Version 1 reference, standards updated	C264.02.1	M		
	Hold Point added	C264.04.1	A		
	Specification Version 1 reference, Hold Points and Witness Points added	C264.05	A		
	Witness Points added	C264.06	A		
	Specification Version 1 reference	C264.07	A		
	Witness Point added	C264.08.5	A		
	Hold Point added	C264.09.2	A		
	Requirements for wire rope added. Hold Point added	C264.11.1	A		
	Specification Version 1 reference	C264.16	A		
Annexure added	C264 - A	A			
VERSION 2	References to QPRC Updated		M	CS	12/03/18

**SPECIFICATION C264 – NON-RIGID ROAD SAFETY BARRIER SYSTEMS
(Public Domain) – VERSION 2**

CLAUSE	CONTENTS	PAGE
GENERAL		1
C264.01	SCOPE	1
C264.02	REFERENCE DOCUMENTS	1
MATERIALS		2
C264.03	COMPONENTS	2
C264.04	CERTIFICATION	2
CONSTRUCTION		2
C264.05	GENERAL	2
C264.06	ERECTION OF STEEL POSTS	2
C264.07	ERECTION OF TIMBER POSTS	3
C264.08	ERECTION OF ROAD SAFETY BARRIER RAILS	3
C264.09	END TREATMENT OF ROAD SAFETY BARRIERS	4
C264.10	DELINEATORS	4
SPECIAL REQUIREMENTS		5
C264.11	RESERVED	5
C264.12	RESERVED	5
C264.13	RESERVED	5
C264.14	RESERVED	5
LIMITS AND TOLERANCES		5
C264.15	SUMMARY OF LIMITS AND TOLERANCES	5
MEASUREMENT AND PAYMENT		6
C264.16	PAY ITEMS	6
ANNEXURE		8
C264-A	INSPECTIONS	8

SPECIFICATION C264: NON-RIGID ROAD SAFETY BARRIER SYSTEMS (Public Domain) – VERSION 2

GENERAL

C264.01 SCOPE

1. The work to be executed under this Specification consists of the setting out, supply of all materials and erection of road safety barriers and terminals, in accordance with the requirements for non-rigid road safety barrier systems in AS/NZS 3845, at the locations shown on the Drawings or as directed by the Superintendent.

2. This Specification details the requirements for public domain non-rigid road safety barrier systems. Where a patented non-rigid road safety barrier system is specified and shown on the Drawings, all materials shall be in accordance with the manufacturer's specifications and, it shall be constructed strictly in accordance with the manufacturer's instructions.

3. The Contractor shall give notice so that inspection may be made of all **HOLD POINTS** and **WITNESS POINTS** documented in this specification and tabulated in Annexure C264-A.. Release of **HOLD POINTS** and **WITNESS POINTS** shall be made by the Superintendent, with the concurrence of the Principal Certifying Authority to be obtained, where stipulated in Annexure C264-A.

Inspections

C264.02 REFERENCE DOCUMENTS

1. Documents referenced in this Specification are listed in full below, whilst being cited in the text in the abbreviated form or code indicated.

*Documents
Standards Test
Methods*

(a) Council Specifications

C201	-	Control of Traffic - Version 2
C271	-	Minor Concrete Works - Version 2

(b) Australian Standards

AS1214:1983	Hot-dip galvanised coatings on threaded fasteners (ISO metric course thread series)
AS/NZS1594:2002	Hot-rolled steel flat products
AS 1627	Metal finishing – Preparation and pre-treatment of surfaces
AS1627.4-2005	Abrasive cleaning of steel
AS1627.5-2003	Pickling
AS/NZS 1906	Retroreflective materials and devices for road traffic control purposes
AS/NZS 1906.2:2007	Retroreflective devices (non pavement application).
AS 2858:2008	Timber–softwood – visually stress-graded for structural purposes
AS 2311:2009	Guide to the painting of buildings
AS 3730	Guide to the properties of paints for buildings
AS 3730.10:2006	Latex – Exterior – Gloss
AS 3730.18:2006	Undercoat / Sealer – Latex - Interior
AS/NZS 3845:1999	Road safety barrier systems.
AS/NZS 4680:2006	Hot-dip galvanised (zinc) coatings on fabricated ferrous articles

MATERIALS**C264.03 COMPONENTS**

1. All steel components for public domain non-rigid road safety barrier systems, W-beam and Thrie-beam, shall be in accordance with AS/NZS 3845 and shall be of the type as shown on the Drawings. **Steel**
2. Timber posts are to be used only in W-beam terminal sections, as detailed on the Drawings and shall be of the timber type, grade, size and treatment level in accordance with AS/NZS 3845. All surfaces shall be smooth and free from obvious saw marks. **Timber**

C264.04 CERTIFICATION

1. Steel and timber road safety barrier components shall not be erected until the Contractor has produced documentary evidence to the Superintendent that the steel and timber road safety barrier components conform to the requirements of this Specification. This is a **HOLD POINT**. **Evidence of Conformance (HP)**

CONSTRUCTION**C264.05 GENERAL**

1. The Contractor shall at all times conform to the requirements of the Specification for CONTROL OF TRAFFIC - VERSION 2. **Traffic Control**
2. Construction of non-rigid road safety barrier shall comply with AS/NZS 3845 except where explicit departures are detailed on the Drawings.
3. Road safety barriers shall be erected after the construction of the base on concrete pavements and after the placing of the initial layer of asphaltic concrete or sprayed seal on a flexible pavement, unless otherwise approved by the Superintendent. This is a **WITNESS POINT**. **Timing of Construction (WP)**
4. The Contractor shall set out the work to ensure that all road safety barriers and terminal sections are located in accordance with the Drawings or as directed by the Superintendent. Peg or paint mark the start and finish points and line of safety barrier, transitions and terminals including the line of flare if applicable. This is a **HOLD POINT**. **Set Out (HP)**
5. Underground cables and ducts laid in the road safety barrier area shall be located prior to the erection of posts and all care must be taken not to damage such cables and ducts. This is a **HOLD POINT**. **Cables and Ducts (HP)**
6. The posts should be set to the full depth as shown on the Drawings. If this is not possible due to the presence of an underground obstruction, an alternative method of setting the posts, as approved by the Superintendent, shall be used. This is a **WITNESS POINT**. **Underground Obstruction (WP)**
7. Posts shall stand vertical and the spacing shall be such that when the safety barrier is erected no post movement is necessary in order to align holes or for any other reason. **Post Accuracy**

C264.06 ERECTION OF STEEL POSTS

1. The safety barrier posts are to be located as shown on the Drawings. The top of the post shall be 710mm, 805mm or 865mm as appropriate for W-beam, Thrie-beam or modified blockout Thrie-beam respectively, above the ground level, unless otherwise **Positioning of Posts**

shown on the Drawings. On terminal ends, the level of the posts shall be such as to conform to the extended crossfall of the main pavement unless otherwise shown on the Drawings.

- | | |
|---|---|
| <p>2. When erected in position the posts shall be on a smooth line both horizontally and vertically with the tops of posts within ± 20mm of the heights specified in paragraph 1 of this Clause.</p> | <p>Smooth Line/
Tolerances</p> |
| <p>3. Steel posts shall be erected by driving, or by other means, as directed by the Superintendent, in accordance with the requirements for foundation posts in AS/NZS 3845. This is a WITNESS POINT. The open section of the post shall point in the same direction as adjacent traffic. The posts are to be firm in the ground and any movement at ground level shall not exceed 3mm in any direction when force tested in accordance with AS/NZS 3845.</p> | <p>Foundation
and Testing
(WP)</p> |
| <p>4. The posts shall not have any obvious deformation as a result of driving. Any damage which does occur to the posts is to be repaired within 24 hours using an organic zinc-rich primer in accordance with the repair requirements of Appendix E in AS/NZS 4680.</p> | <p>Damage to
Posts</p> |
| <p>5. Any post which has been excessively damaged will be rejected by the Superintendent and shall be replaced by the Contractor at its own expense. This is a WITNESS POINT.</p> | <p>Contractor's
Cost (WP)</p> |

C264.07 ERECTION OF TIMBER POSTS

- | | |
|--|--|
| <p>1. The safety barrier posts are to be located as shown on the Drawings. The top of the posts shall be 710mm ± 20mm above the ground level, unless otherwise shown on the Drawings. On terminal ends the level of the posts shall be such as to conform to the extended crossfall of the main pavement, unless shown otherwise on the Drawings.</p> | <p>Positioning of
Posts</p> |
| <p>2. When erected in position the posts shall be on a smooth line both horizontally and vertically.</p> | <p>Smooth Line</p> |
| <p>3. The section of the timber posts to be cast into a reinforced concrete footing shall be wrapped in 12mm thick polystyrene foam sheeting before concrete casting.</p> | <p>Polystyrene
Foam</p> |
| <p>4. Concrete used in the footings for timber posts shall have a minimum compressive strength of 32MPa at 28 days and shall conform with the requirements of the Specification for MINOR CONCRETE WORKS - VERSION 2.</p> | <p>Concrete</p> |
| <p>5. Concrete footings shall be 600mm diameter, and shall have tolerances of minus zero or plus 50mm. Overbreak and excessive depth shall be filled with 32MPa concrete at no cost to the Principal.</p> | <p>Footing Size</p> |
| <p>6. Wire fabric reinforcing shall be as detailed on the Drawings.</p> | <p>Reinforcing
Fabric</p> |
| <p>7. The surface area of the posts which will be above ground shall be painted with two coats of grey acrylic paint.</p> | <p>Painting</p> |

C264.08 ERECTION OF ROAD SAFETY BARRIER RAILS

- | | |
|---|-------------------------|
| <p>1. Steel blackout pieces shall be erected with the open section pointing in the same direction as adjacent traffic.</p> | <p>Blockouts</p> |
| <p>2. All rail laps shall be in the same direction as adjacent traffic such that approach rail ends are not exposed to traffic.</p> | <p>Rail Laps</p> |

NON-RIGID ROAD SAFETY BARRIER SYSTEMS

- | | | |
|----|---|------------------------------------|
| 3. | Stiffening pieces, 300mm long, shall be used on intermediate posts. | Stiffening Pieces |
| 4. | Road safety barrier rails and blockout pieces shall be handled and erected in such a manner that no damage occurs to the galvanising. Any minor damage occasioned to the galvanising shall be repaired within 24 hours using an organic zinc-rich primer in accordance with the repair requirements of Appendix E in AS/NZS 4680. | Minor Damage to Galvanising |
| 5. | Any road safety barrier rails or blockout pieces which have been excessively damaged will be rejected by the Superintendent and shall be replaced by the Contractor at its own expense. This is a WITNESS POINT . | Contractor's Cost (WP) |
| 6. | Road safety barrier rail attachment bolts and splice bolts are to be tightened initially such that the barrier can be erected. Adjustments are then to be made to the rails using the slotted holes provided to produce a smooth regular line, free of any kinks or bumps. The overall line of the top of the safety barrier rails is to visually conform with the vertical alignment of the road pavement. | Erection Procedure |
| 7. | When the alignment both vertically and horizontally is obtained the splice bolts are to be fully tightened. The bolt head (not the shoulder) should be in full bearing with the rail. | Splice Bolt Tightening |

C264.09 END TREATMENT OF ROAD SAFETY BARRIERS

- | | | |
|----|---|--------------------------------------|
| 1. | Both approach and departure ends of the road safety barrier shall be constructed with leading and trailing terminal sections at locations shown and as detailed on the Drawings. | Leading, Trailing Terminals |
| 2. | Modified eccentric loader terminals (MELT) shall be constructed, as detailed on the Drawings and, at approach end locations of road safety barriers as shown on the Drawings. Where the departure end of a road safety barrier is within the clear zone of opposing traffic, a MELT shall be constructed in place of a trailing terminal section. Submit locations prior to ordering. This is a HOLD POINT . | MELT (HP) |
| 3. | The approach and departure ends of double sided road safety barriers shall have terminal sections as detailed on the Drawings. | Double Sided Safety Barrier |
| 4. | Non-rigid road safety barrier connections to rigid road safety barriers or bridge parapets shall be as detailed on the Drawings. | Connections to Rigid Barriers |

C264.10 DELINEATORS

- | | | |
|----|---|---------------|
| 1. | Delineators complying with AS 1906.2 shall be fixed with brackets to the road safety barrier, to the details and at the locations shown on the Drawings beginning at the first post and then in accordance with the following table:- | Fixing |
|----|---|---------------|

Radius of Curve	Spacing of Reflectors on Barrier
m	every
30 - 90	3rd post
90 - 180	5th post
180 - 275	8th post
275 - 365	11th post
over 365	16th post
(including straight road)	

- | | | |
|----|---|-------------------------------|
| 2. | The delineators shall be so arranged that drivers approaching from either direction will see only red reflectors on their left side, and white reflectors on their right. | Arrangement and Colour |
|----|---|-------------------------------|

SPECIAL REQUIREMENTS

C264.11 INSTALLATION OF WIRE ROPE SAFETY BARRIER SYSTEMS

1. Submit certification that the wire rope has been tensioned to conform with the manufacturer's published requirements. The certificate must include the date, time, ambient air temperature, tension force and signature and name of the individual managing the work at the time. This is a **HOLD POINT**.

***Manufacturer's
Published
Requirements
(HP)***

C264.12 RESERVED

C264.13 RESERVED

C264.14 RESERVED

LIMITS AND TOLERANCES

C264.15 SUMMARY OF LIMITS AND TOLERANCES

1. The limits and tolerances applicable to the various clauses in this specification are summarised in Table C264.1 below:

Item	Activity	Limits/Tolerances	Spec Clause
1.	Vertical Alignment		
	(a) Tops of steel posts.	± 20mm	C264.06
	(b) Tops of timber posts	± 20mm	C264.07
2.	Post Movement	≤ 3mm	C264.06
3.	Concrete Footings		
	(a) Diameter	-0mm or +50mm	C264.07

Table C264.1 - Summary of Limits and Tolerances

MEASUREMENT AND PAYMENT**C264.16 PAY ITEMS**

1. Payment shall be made for all the activities associated with completing the work detailed in this Specification on a schedule of rates basis in accordance with Pay Items C264(a) to C264(g) inclusive.
2. A lump sum price for any of these items shall not be accepted.
3. If any item, for which a quantity of work listed in the Schedule of Rates, has not been priced by the Contractor, it shall be understood that due allowance has been made in the prices of other items for the cost of the activity which has not been priced.
4. Concrete footings for timber posts are measured and paid in accordance with this Specification and not in the Specification for MINOR CONCRETE WORKS - VERSION 2.
5. Miscellaneous minor concrete work not included in the pay items in this Specification shall be in accordance with pay items described in the Specification for MINOR CONCRETE WORKS - VERSION 2.
6. Traffic control is measured and paid in accordance with the Specification for CONTROL OF TRAFFIC - VERSION 2.

Pay Item C264(a) SINGLE SIDED ROAD SAFETY BARRIER

- (i) Single W-beam
- (ii) Nested W-beam
- (iii) Single Thrie-beam
- (iv) Nested Thrie-beam
- (v) Single Modified Blockout Thrie-beam
- (vi) Nested Modified Blockout Thrie-beam
- (vii) Single W-Thrie-beam Transition
- (viii) Nested W-Thrie-beam Transition

1. The unit of measurement shall be the linear metre.
2. The distance shall be measured along the centre line of the rail, centre to centre of posts, excluding terminal sections and connectors to rigid safety barriers or bridge parapets..
3. The schedule rate shall include the supply of all components and fixings and all activities associated with the erection of each type of road safety barrier.

Pay Item C264(b) MODIFIED ECCENTRIC LOADER TERMINAL (MELT)

1. The unit of measurement shall be "each" MELT section supplied and erected as detailed on the Drawings.

Pay Item C264(c) TERMINAL SECTION

- (i) Leading Terminal
- (ii) Trailing Terminal

1. The unit of measurement shall be "each" terminal section supplied and erected as detailed on the Drawings.

Pay Item C264(d) CONNECTORS TO RIGID ROAD SAFETY BARRIERS (RSB) OR BRIDGE PARAPET

- (i) W-beam to RSB
- (ii) W-beam to Thrie-beam to RSB
- (iii) Thrie-beam to RSB

1. The unit of measurement shall be "each" connector supplied and erected as detailed on the Drawings, excluding the anchorage assemblies cast into the rigid road safety barrier or bridge parapet.

Pay Item C264(e) DELINEATOR BRACKETS

1. The unit of measurement shall be "each".

Pay Item C264(f) DOUBLE SIDED ROAD SAFETY BARRIER

- (i) Single W-beam
- (ii) Nested W-beam
- (iii) Single Thrie-beam
- (iv) Nested Thrie-beam
- (v) Single Modified Blockout Thrie-beam
- (vi) Nested Modified Blockout Thrie-beam
- (vii) Single W-Thrie-beam Transition
- (viii) Nested W-Thrie-beam Transition

1. The unit of measurement shall be the linear metre.

2. The distance shall be measured along the centre line of the rails, centre to centre of posts, excluding terminal sections and connectors to rigid safety barriers or bridge parapets.

3. The schedule rate shall include the supply of all components and fixings and all activities associated with the erection of each type of road safety barrier.

Pay Item C264(g) DOUBLE SIDED ROAD SAFETY BARRIER TERMINAL SECTION

1. The unit of measurement shall be "each" terminal section supplied and erected as detailed on the Drawings.

INSPECTIONS

Give notice so inspection may be made of the following:

Summary of HOLD POINTS

Item/Clause title	Requirement	Notice for inspection	Release by
MATERIALS			
Certification			
C264.04.1 – Evidence of Conformance	Provide documentary evidence of conformity of components	1 week prior to erection	Superintendent
CONSTRUCTION			
General			
C264.05.4 – Set Out	Obtain approval to set out	1 week prior to erection	Superintendent
C264.05.5 – Cables and Ducts	Locate underground services	5 working days prior to erection	Superintendent
End treatment of road safety barriers			
C264.09.2 - MELT	Submit alternative MELT locations	1 week prior to ordering	Superintendent
SPECIAL REQUIREMENTS			
Installation of wire rope safety barrier systems			
C264.11.1 - Manufacturers Published Requirements	Submit tension certificates and testing	Same day as tensioning	Superintendent

Summary of WITNESS POINTS

Item	Requirement	Notice for inspection
CONSTRUCTION		
General		
C264.05.3 – Timing of Construction	Erection after pavement activities	1 week before installation – progressive
C264.05.6 – Underground Obstruction	Alternative method due to obstructions	1 week before setting posts
Erection of Steel Posts		
C264.06.3 – Foundation and Testing	Equipment and procedure for erection	1 week before installation
C264.06.5 – Contractor’s Cost	Assessment by Superintendent for replacement	3 working days before removal of damaged post
Erection of Road Safety Barrier Rails		
C264.08.5 – Contractor’s Cost	Assessment and rejection by Superintendent	1 working day after perceived damage